



<b>TO</b>	<b>ISAAC VIDER</b>  <b>WESTRALIAN APARTMENTS</b> <b>78 TERRACE RD EAST PERTH</b>
-----------	---

**P.O BOX 697, CANNINGTON, W.A 6987**  
**EMAIL TERRY@ARCONSTRUCT.COM.AU**  
**MOBILE: 0420 390 599**  
**ABN: 15 128 890 737**  
**DATE: 26 FEBRUARY, 2018**

Glass removal and replacement with 10 mm Acrylic system.

1. Removal and disposal of all Glass from Ground floor Canopy.
2. Installation of new 10mm Acrylic system including new glazing bars, glazing rubbers and endcaps.
3. All Metal components clear anodized or powder coated.
4. Any Span over 3050mm long will need to be joined with suitable metal joiner.
5. All waste removed.
6. Quotation includes hire of crane.
7. 10 year workmanship warranty.
8. Manufacturer's warranty on all products.

Price \$37,800.00 Plus GST

A 50% Deposit is required on confirmation of order.  
Remainder to be paid on completion and due on receipt of Invoice.  
An area will need to be set aside for skip bin and crane usage.